In class practice 1

Project activities of a project have been calculated as in table in below. The contractor has won the project at the price of 250 MT. Client will pay 20% of the project cost as down payment in advance; 20% cost of the project will be paid after the completion of the activity C; and the rest of the project price will be paid at the end of the project. Calculate the cash flow of the project! What is going to be the maximum cash in hand required?

Task Name	1	2	3	4	5	6	7	8	9	10	11	Cost (MT)
A												$80.00
B												$32.00
C												$40.00
D												$36.00
E												$60.00